

## क्षेत्रीय जैवप्रौद्योगिकी केन्द्र

राष्ट्रीय महत्ता की संस्था, जैवप्रौद्योगिकी विभाग,  
भारत सरकार द्वारा यूनेस्को के तत्वावधान में स्थापित

### Regional Centre for Biotechnology

An Institution of National Importance  
Established by the Department of Biotechnology  
Government of India Under the auspices of UNESCO



United Nations  
Educational, Scientific and  
Cultural Organization



क्षेत्रीय जैव प्रौद्योगिकी केन्द्र  
Regional Centre  
for Biotechnology

## कोटेशन आमंत्रण सूचना Notice Inviting Quotation

NIQ No. 03

File No. RCB-17022/13/2025-ENGG-RCB

E-COMP No. 34892

Date: - 30/05/2025

कार्य का नाम:- आरसीबी में वर्टिकल ब्लाइंड्स पर्दे की आपूर्ति और स्थापना, तथा ग्लास के साथ विंडो पैनल की स्थापना।

**Name of Work: -Supply and fixing of Vertical blinds curtain, and window panel with glass at RCB Building at Bio Cluster Faridabad.**

उपरोक्त कार्य हेतु विभिन्न विक्रेता/एजेंसी से दर कोटेशन आमंत्रित किया गया है।

Rate quotations are invited from various vendors/agencies for the below detailed work.

### Schedule of work

Sr. No.	Description of Item	Unit	Quantity	Rate	Amount
1	Supply and fixing of grey coloured Vertical blind curtains for Windows as per the Specifications attached as Annexure-1.	sqm	25		
2	Dismantling walls make cut-out for windows and finish with plaster and paint as per the direction of engineer-in-charge.	Rmt	20		
3	Supply and Fixing of four black painted Glazed Aluminium windows in 40x40mm x 2 mm outer frame with 4mm glass.	sqm	5		

Amount

GST

Total Amount

*Signature*

एन०सी०आर० बायोटेक साइंस क्लस्टर, फरीदाबाद-121001, हरियाणा, भारत NCR Biotech Science Cluster, Faridabad-121001, Haryana, India

दूरभाष : +91 129 2848800 ईमेल E: registrar@rcb.res.in वेबसाइट www.rcb.res.in

### नियम और शर्तें

- 1 कार्य कार्य अनुसूची, विनिर्देश और प्रभारी अभियंता के निर्देश के अनुसार पूरा किया जाएगा।
- 2 विक्रेताओं को सलाह दी जाती है कि वे अपना रेट कोटेशन जमा करने से पहले साइट पर जाकर प्रस्तावित कार्य का मूल्यांकन करें।
- 3 एजेंसी द्वारा अनुबंधों को उनकी कंपनी के लेटरहेड पर सावधानीपूर्वक भरा जाएगा और सील किया जाएगा NIQ दस्तावेज़ 13.06.2025, 11.00 am बजे और उससे पहले आरसीबी रिसेप्शन पर जमा किए जाने चाहिए
- 4 कार्य का विचलन - कुल कार्य ऑर्डर मूल्य के  $\pm 10$  के विचलन की अनुमति दी जा सकती है।
- 5 कोई अग्रिम भुगतान नहीं किया जाएगा।
- 6 भुगतान वास्तविक कार्य एवं माप के अनुसार किया जाएगा।
- 7 सुरक्षा जमा- पूर्ण कार्य राशि का 10% अंतिम बिल भुगतान से काटा जाएगा और 3 महीने की दोष देयता अवधि (डीएलपी) के पूरा होने के बाद जारी किया जाएगा।
- 8 दोष दायित्व अवधि (डीएलपी) के दौरान, यदि एजेंसी द्वारा निष्पादित कार्य में कोई कार्य क्षतिग्रस्त/मरम्मत योग्य पाया जाता है, तो एजेंसी को अपनी लागत पर इसकी मरम्मत करानी होगी। आरसीबी द्वारा एजेंसी को अलग से भुगतान नहीं किया जाएगा
- 9 भारत सरकार के नियमों के अनुसार बिल से आयकर काटा जाएगा, जिसके लिए ठेकेदार/आपूर्तिकर्ता को टीडीएस जमा करने के लिए एनआईक्यू के साथ मालिक की पंजीकृत कंपनी के नाम पर पैन नंबर और जीएसटी प्रमाण पत्र की एक प्रति प्रदान करनी होगी।
- 10 दर में सामग्री, श्रम, माल ढुलाई, कार्टेज, लोडिंग अनलोडिंग, मचान और फिक्सिंग आदि शामिल होना चाहिए। जीएसटी भाग को अलग से दिखाया जाना चाहिए।
- 11 कार्य पूरा करने के लिए कार्य आदेश जारी होने की तारीख से 20 दिन का समय दिया जाएगा।
- 12 कार्य के लिए दिए गए समय का सख्ती से पालन किया जाएगा अन्यथा ठेकेदार को विलंब के प्रति दिन कार्य के आदेशित मूल्य का 0.2% की दर से मुआवजा देना होगा, जो कुल आदेशित मूल्य का अधिकतम 5% होगा।





### **TERMS AND CONDITIONS**

1. The work shall be completed as per the Schedule of Work, specification and instruction of Engineer-In-charge.
2. Venders are advised to visit the site to assess the proposed work before submitting their rate quotation.
3. **Annexures should be filled out by agency carefully on their company letterhead and sealed NIQ documents should be submitted at RCB reception on 13/06/2025 and before 11.00 am.**
4. Deviation of Work - deviation can be allowed of  $\pm 10$  of total work order value.
5. No Advance payment shall be made.
6. Payment will be made as per the actual work done and measured.
7. Security deposit- 10% of the completed work amount will be deducted from final bill payment and will be released after completion of Defects Liability Period (DLP) of 3 Months.
8. During the defects liability period (DLP), if any work found in damage/repairable of work executed by agency, the agency will have provided and repaired it at its own cost. The agency will not be paid separately by RCB.
9. Income tax shall be deducted from the bill as per GOI rules for which contractor/supplier should have provided a copy of PAN No. and GST certificate in the name of registered company of proprietor along with NIQ for depositing TDS.
10. The rate should be included in material, labor, freight, cartage, loading unloading, scaffolding and fixing etc. The GST part should be shown separately.
11. Time allowed for completion for work shall be 20 days from date of issue of Work order.

R/K

12. The time allowed for the work shall be strictly followed otherwise the Contractor shall be liable to pay compensation at the rate of 0.2% of the ordered value of the work per day of delay on the part of the contractor subject to a maximum of 5% of the total ordered value.



**Executive Engineer/I.E**

रमेश कुमार राठौर / Ramesh Kumar Rathore  
कार्यकारी अभियन्ता / Executive Engineer  
क्षेत्रीय जैवप्रौद्योगिकी केंद्र / Regional Centre for Biotechnology  
(जैवप्रौद्योगिकी विभाग, भारत सरकार द्वारा यूनेस्को के तत्वावधान में स्थापित)  
(Esid. by the Dept. of Biotechnology, Govt of India, under the auspices of UNESCO)  
एन. सी. आर. बायोटेक साइंस क्लस्टर, 'N.C.R. Biotech Science Cluster'  
तृतीय मील पथ, फरीदाबाद-गुडगांव एक्सप्रेसवे  
3<sup>rd</sup> Milestone, Faridabad-Gurgaon Expressway  
फरीदाबाद - 121 001 हरियाणा / Faridabad - 121 001 Haryana

## Vertical Blinds - Specifications

S. No.	Description of Item	Desired specification
1	Blinds Type	Vertical blinds
2	Recommended Make	Vista, Ddecor, Asian Paints, Hunter Douglas
3	Fabric	<p>1. Composition: 100% Polyester made up of fibre dyed yarn to prevent fabric from fading with Acrylic coating on both sides.</p> <p>2. Min. Fabric Thickness: 0.9 mm</p> <p>3. Min. Fabric Weight: 400 GSM</p> <p>4. Fabric/Slat Width: 100 mm</p> <p>5. Warp &amp; Weft : 2/15</p> <p>Fabric width -100mm fabric thickness 0.9 mm, fabric weight 425 GSM +- 5%, Warp 2/15 Weft 2/15</p>
4	End Control Unit	End control/Reduction gear box having the reduction ratio of 3.5:1 for a very smooth operation of the blind. This unit shall consist of a planetary gear in the outer housing, four small transmission gears fitted in the middle assembly and an end receiving gear attached to central sprocket unit.
5	Head Rail	Head Rail: Head rail is of 25mm high and 47 mm wide extruded High strength aluminium alloy section with average wall thickness of minimum 0.9mm. The section is anodized for smooth operations and has the provision of shades valance matching with louvers.
6	Carrier (Runner)	It shall consist of polymer housing with wheels mounted on sides and has a gear and worm mechanism with vertical worm fixed with a tongued poly carbonate stem to hold the louvers. The worm and gear mechanism are driven by tilt rod fixed to end control unit to rotate louvers by 180 degrees. The mounted wheels on sides of casing move on rails of head rail section for resistance free stacking of louvers.
7	Tilt Rod	It is made of extruded aluminium having three keyways. The tilt rod is fixed in the end control unit and drives the carrier gear mechanism to rotate the louvers. The average diameter is 5.8mm to achieve minimum torsion deflection.

P/10



8	Tilter chain	To be made up of 4.5 mm plastic beads moulded on 1.5 mm thick polyester cord. The Pitch of the beads is 6mm. The chain drives the sprocket fixed in the end control unit to rotate the louvers by 180 degrees. The pitch of the chain shall correspond to the sprocket in perfect match for trouble free operation. Colour: White
<b>Special Instructions</b>		
1	The quote shall include cost of material, labour, taxes, delivery, overheads and wastage if any.	
2	Nothing extra shall be paid and the bidder shall be liable to incur all the expenses required in satisfactory completion of the work.	
3	Vendor to fabricate the blinds as per actual site measurements of windows and get the sample of blinds approved from the Department before supply.	
4	Payment to be made as per actual area of blinds installed at site as per size specified.	

*P/20*