

## क्षेत्रीय जैवप्रौद्योगिकी केन्द्र

राष्ट्रीय महत्ता की संस्था, जैवप्रौद्योगिकी विभाग,  
भारत सरकार द्वारा यूनेस्को के तत्वावधान में स्थापित

### Regional Centre for Biotechnology

An Institution of National Importance  
Established by the Department of Biotechnology  
Government of India Under the auspices of UNESCO



United Nations  
Educational, Scientific and  
Cultural Organization



क्षेत्रीय जैव प्रौद्योगिकी केन्द्र  
Regional Centre  
for Biotechnology

### कोटेशन आमंत्रण सूचना Notice Inviting Quotation

NIQ No. 05

File No. RCB-17022/12/2025-ENGG-RCB

E-COMP No. 34457

Date: - 03/06/2025

कार्य का नाम:- बायोटेक क्लस्टर, फरीदाबाद में आरसीबी भवन में फायर हाइड्रेंट लाइन का पुनः संचालन कार्य।  
**Name of Work: -Re-Operational Work of Fire Hydrant Line at RCB building at Biotech Cluster, Faridabad.**

उपरोक्त कार्य हेतु विभिन्न विक्रेता/एजेंसी से दर कोटेशन आमंत्रित किया गया है।

Rate quotations are invited from various vendors/agencies for the below detailed work.

#### Schedule of work

S.No.	Description	Unit	Quantity	Rate	Amount
1	<b>Job:1 (Joining one dummy Fire hydrant line to operating Fire hydrant Line from Ground to the slab by proving one additional vertical line after cutting core through the walls)</b> Providing, laying, jointing, testing and commissioning of following sizes of pipes M.S Heavy C Class conforming to IS-1239 & 3589 (5.35mm thick), as per specifications along with necessary fittings including fixing the pipe on floor / wall /ceiling with clamps, hangers (using anchor fasteners) as per specification. Pipes to be duly tested to 1.5 times of working pressure, in an approved manner as per given drawings, specifications and instruction of the engineer in charge. Supply & applying of one coat of primer & two coat paint on below mentioned size of MS C Class Pipe fixed for the given system.				
(A)	150 mm dia. (C Class Heavy) , MAKE: - Jindal Hissar, Parkash Surya	Rmt	18		
(C)	Dismantling Hydrant Pipe at both ends of Joining and joining new pipe including welding	Job	1		

(D)	Earth Excavation with filling after work, wall core cutting 150 mm dia	Job	1		
(E)	MS Dummy Flange 150mm	No.	1		
(F)	POP work cutting and repairing	Sq mt.	3.6		
(G)	Primer and paint work	Sq mt.	3.6		
2.	<b>Job 2 (Repairing of Leakage by providing new pipe under Ground Line underneath Ground Approx. 6-7 feet after cutting the Line)</b> Providing, laying, jointing, testing and commissioning of following sizes of pipes M.S Heavy C Class conforming to IS-1239 & 3589 (5.35mm thick), as per specifications along with necessary fittings including fixing the pipe on floor / wall / ceiling with clamps, hangers (using anchor fasteners) as per specification. Pipes to be duly tested to 1.5 times of working pressure, in an approved manner as per given drawings, specifications and instruction of the engineer in charge. Supply & applying of one coat of primer & two coat paint on below mentioned size of MS C Class Pipe fixed for the given system.				
(A)	150 mm dia. (C Class Heavy) , MAKE: - Jindal Hissar, Parkash Surya	Rmt	6		
(B)	Dismantling Hydrant Pipe at both ends of Joining and joining new pipe including welding	Job	1		
(C)	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and filling with good soil after work and disposal of surplus excavated soils as directed, within a lead of 50 m.	cumec	10		

Amount

GST

Total Amount



### नियम और शर्तें

- 1 कार्य कार्य अनुसूची, विनिर्देश और प्रभारी अभियंता के निर्देश के अनुसार पूरा किया जाएगा।
- 2 विक्रेताओं को सलाह दी जाती है कि वे अपना रेट कोटेशन जमा करने से पहले साइट पर जाकर प्रस्तावित कार्य का मूल्यांकन करें।
- 3 एजेंसी द्वारा अनुबंधों को उनकी कंपनी के लेटरहेड पर सावधानीपूर्वक भरा जाएगा और सील किया जाएगा NIQ दस्तावेज़ 10.06.2025, 11.00 am बजे और उससे पहले आरसीबी रिसेप्शन पर जमा किए जाने चाहिए
- 4 कार्य का विचलन - कुल कार्य ऑर्डर मूल्य के  $\pm 10\%$  के विचलन की अनुमति दी जा सकती है।
- 5 कोई अग्रिम भुगतान नहीं किया जाएगा।
- 6 भुगतान वास्तविक कार्य एवं माप के अनुसार किया जाएगा।
- 7 सुरक्षा जमा- पूर्ण कार्य राशि का 10% अंतिम बिल भुगतान से काटा जाएगा और 3 महीने की दोष देयता अवधि (डीएलपी) के पूरा होने के बाद जारी किया जाएगा।
- 8 दोष दायित्व अवधि (डीएलपी) के दौरान, यदि एजेंसी द्वारा निष्पादित कार्य में कोई कार्य क्षतिग्रस्त/मरम्मत योग्य पाया जाता है, तो एजेंसी को अपनी लागत पर इसकी मरम्मत करानी होगी। आरसीबी द्वारा एजेंसी को अलग से भुगतान नहीं किया जाएगा
- 9 भारत सरकार के नियमों के अनुसार बिल से आयकर काटा जाएगा, जिसके लिए ठेकेदार/आपूर्तिकर्ता को टीडीएस जमा करने के लिए एनआईक्यू के साथ मालिक की पंजीकृत कंपनी के नाम पर पैन नंबर और जीएसटी प्रमाण पत्र की एक प्रति प्रदान करनी होगी।
- 10 दर में सामग्री, श्रम, माल ढुलाई, कार्टेज, लोडिंग अनलोडिंग, मचान और फिक्सिंग आदि शामिल होना चाहिए। जीएसटी भाग को अलग से दिखाया जाना चाहिए।
- 11 कार्य पूरा करने के लिए कार्य आदेश जारी होने की तारीख से 20 दिन का समय दिया जाएगा।
- 12 कार्य के लिए दिए गए समय का सख्ती से पालन किया जाएगा अन्यथा ठेकेदार को विलंब के प्रति दिन कार्य के आदेशित मूल्य का 0.2% की दर से मुआवजा देना होगा, जो कुल आदेशित मूल्य का अधिकतम 5% होगा।

### TERMS AND CONDITIONS

1. The work shall be completed as per the Schedule of Work, specification and instruction of Engineer-In-charge,



2. Venders are advised to visit the site to assess the proposed work before submitting their rate quotation.
3. **Annexures should be filled out by agency carefully on their company letterhead and sealed NIQ documents should be submitted at RCB reception on 10/06/2025 and before 11.00 am.**
4. Deviation of Work - deviation can be allowed of  $\pm 10\%$  of total work order value.
5. No Advance payment shall be made.
6. Payment will be made as per the actual work done and measured.
7. Security deposit- 10% of the completed work amount will be deducted from final bill payment and will be released after completion of Defects Liability Period (DLP) of 3 Months.
8. During the defects liability period (DLP), if any work found in damage/ repairable of work executed by agency, the agency will have provided and repaired it at its own cost. The agency will not be paid separately by RCB.
9. Income tax shall be deducted from the bill as per GOI rules for which contractor/supplier should have provided a copy of PAN No. and GST certificate in the name of registered company of proprietor along with NIQ for depositing TDS.
10. The rate should be included in material, labor, freight, cartage, loading unloading, scaffolding and fixing etc. The GST part should be shown separately.
11. Time allowed for completion for work shall be 20 days from date of issue of Work order.
12. The time allowed for the work shall be strictly followed otherwise the Contractor shall be liable to pay compensation at the rate of 0.2% of the ordered value of the work per day of delay on the part of the contractor subject to a maximum of 5% of the total ordered value.



**Executive Engineer/I.E**

अविनाश कुमार कोडिकल / Avinash Kumar Kodikal,  
उपकरण अभियंता / Instrumentation Engineer,  
क्षेत्रीय जैवप्रौद्योगिकी केन्द्र / Regional Centre for Biotechnology,  
जैवप्रौद्योगिकी विभाग, भारत सरकार / Department of Biotechnology, Govt. of India  
फरीदाबाद-१२१००१ (भारत) / Faridabad-121001 (India)  
Ph.: 0129-2848932 | Email : avinashk@rcb.res.in