



REGIONAL CENTRE FOR BIOTECHNOLOGY

NCR-Biotech Science Cluster, 3rd Milestone Faridabad-Gurgaon Expressway, P.O. Box No.04 Faridabad-121001, Haryana, India
Ph: +91-129-2848813

SUPPLY ORDER

ORDER NO: RCB/EQ/55/20-21/RV(COMMON)

DATE 2021/03/24

To,
M/S M/S BHANU BIOTECH PRIVATE LIMITED,
267, BANK ENCLAVE, LAXMI NAGAR, DELHI -110092
EMAIL: --
MOBILE: 98100095572

AMENDED SUPPLY ORDER

DEAR SIR,

WITH REFERENCE TO TENDER NO. **RCB/NIT/20/20-21/SH**; FOR SUPPLY INSTALLATION AND COMMISSIONING; OF FOLLOWING ITEMS, PRICE AS MENTIONED THERE IN TO THE LABORATORY OF OUR INSTITUTE. WE ARE PLEASED TO PLACE ORDER FOR SUPPLY / INSTALLATION OF THE SAME AS PER THE DETAILS AND TERMS & CONDITIONS GIVEN BELOW: -

S. NO.	DESCRIPTION OF ARTICLES	QUANTITY	TOTAL VALUE (INC OF ALL TAXES)
1	SCREENHOUSE	1	7,35,500.00

TOTAL F.O.R OUR INSTITUTE RS. 7,35,500/- (RUPEES SEVEN LAKH THIRTY FIVE THOUSAND FIVE HUNDRED ONLY ALL INCLUSIVE)

BILLING ADDRESS:-

EXECUTIVE DIRECTOR,
REGIONAL CENTRE FOR BIOTECHNOLOGY (RCB)
NCR BIOTECH SCIENCE CLUSTER, 3 RD MILESTONE
FARIDABAD -GURGAON EXPRESSWAY
DISTRICT FARIDABAD 121001 HARYANA

TERMS & CONDITIONS

1. THE ABOVE RATES ARE F.O.R. RCB, FARIDABAD INCLUDING LABOUR, CARTAGE & INSTALLATION IGST ETC.
2. WORK SHALL BE CARRIED OUT AS PER THE FOLLOWING SPECIFICATIONS:

SIZE:

LENGTH : 12.00 METER
WIDTH : 18.00 METER
CENTRE HEIGHT: 04.50 METER
SIDE HEIGHT : 03.30 METER
BAY/ SPAN : 3 X 6.0 METER

ENTRY ROOM: SIZE 2.0 X 2.5M DOUBLE DOOR SYSTEM DOOR SIZE: 1.0MTR X 2.0MTR.

STRUCTURE: MADE OF ISI STANDARD 2.0MM THICK, G.I. SQ. PIPE 47X47MM, 38 X 38MM, 32 X 32MM AND 25 X 25 MM ± 2MM AS PER REQUIREMENT, COMPLETE WITH

COVERING: WITH 40X40 SS (304 GRADE) MESH TO BE FITTED WITH ALUMINUM STRIPS,

FOGGING/SPRINKLING: TO INCREASE THE HUMIDITY UP-TO 80% & PLUSMN; 5% BY PROVIDING 4 WAY FOGGING NOZZLES HANGING TYPE WITH FINE DISCHARGE (28-30 LH) AT 4BAR PRESSURE.

DRIP IRRIGATION SYSTEM: WATER DISCHARGE: INLINE DRIPPER 2 LH EACH NOZZLES SPACING L/L- 0.6M N/N- 0.4M,

HEAD UNIT: DRIP & FOGGING SYSTEM BOTH CONNECTED WITH SINGLE PUMP & TANK

PUMP: 1.5HP

FILTER: DISC ONLINE

WATER STORAGE: PVC TANK 2000 LIT PLACED ON 4-5' HT PLATFORM/ STAND

FERTIGATION: BY VENTURY

MIXING TANK & NBSP: 2 X 200 LIT

TIMER: DIGITAL 0-999 MIN/SEC FOR AUTOMATIC ON/OFF OF DRIP/ FOGGERS PUMP.

ELECTRIC FITTING: PUMP/ TIME SHOULD BE CONNECTED WITH NEAREST POWER SUPPLY POINT (UP-TO 50 MTR)

FOUNDATION: GROUTING OF VERTICAL POLES IN CC 1:2:4 (1 CEMENT: 2 SAND: 4 STONE AGGREGATE 20MM NOMINAL SIZE), 35 X 35 X 70-80CM BELOW GROUND LEVEL.

CURTAIN WALL: MADE OF IN 1:6 CEMENT MORTAR AT ALL SIDES 60 CM ABOVE GL & 45 CM BELOW GL, 23 CM WIDE, WITH PCC BASE 100MM THICK DULY PLASTERED.

LEVELLING: THE INSIDE SCREEN HOUSE & 12 FT HEIGHT GOOD HEALTHY SOIL SHOULD BE FILLED INSIDE THE ENTIRE AREA.

3. DELIVERY / INSTALLATION AND COMMISSIONING OF THE ABOVE-ORDER SHALL BE MADE UPTO **20 MAR 2021**.

4. THE PAYMENT WILL BE MADE AFTER SUPPLY AND SATISFACTORY INSTALLATION & COMMISSIONING, SUBJECT TO CERTIFICATION BY AUTHORISED REPRESENTATIVE OF OUR INSTITUTE.

5. PLEASE SUBMIT INVOICE/BILL IN TRIPLICATE AND PRE-RECEIPTED ALONG WITH COPY OF DM/CHALLAN.

6. **WARRANTY:** 03 YEARS FROM THE DATE OF SUCCESSFULL INSTALLATION AND HANDING OVER TO RCB.

7. THE FIRM SHALL SUBMITT PBG FOR AN AMOUNT EQUIVALENT TO 3% OF THE ORDER VALUE IN THE FORM OF DD/FD/BG IN FAVOR OF EXECUTIVE DIRECTOR RCB FOR A PERIOD OF 39 MONTHS.

NOTE: ORDER IS AMENDED CHANGE IN PO NO.

YOURS SINCERELY,

sd-
Administrative Officer (P)
purchase@rcb.res.in

NOTE: THE SUPPLY ORDER IS SUBJECT TO STANDARD TERMS & CONDITIONS FOR SUPPLY OF ITEMS TO RCB (AS PER SUPPLY ORDER) - [ANNEXURE-I](#)

Distribution:

(a) Supplier Copy

(b) Store Section

(c) Concern User/Department

(d) Account Section

(e) Office Copy

INDENT NO. 8921/RCB

INDENT TYPE: PLANT AND MACHINERY

BUDGET HEAD: COMMON FACILITY

PROVISIONAL GST REG. NO: 06AAAR9016J1ZG

THIS IS A COMPUTER-GENERATED EMAIL/DOCUMENT. NO SIGNATURE IS REQUIRED